



- Builder** completes all pre-lay plumbing and electrical works
- Plumber** to run hot & cold lines to location of iStore tank.
- Electrician** to run new 15A (2.5mm) circuit from electrical meter box to tank location. AC Isolator shall be installed & under no circumstances shall the unit be energized on until tank is filled with water.
- Solargain** to install iStore to Pre-Lay Plumbing specifications and commission unit.
- All valves supplied by Solargain.**